2009 INGAA Foundation Workshop

Building Better Projects Continuous Improvement

March 25, 2009

Houston, Texas

Craig V. Meier Vice President – General Manager Sunland Construction, Inc.



Challenges we have as Construction Contractors

Typically last person involved in the project Route, material, design and extra work space have all been selected and permitted Assembly line type construction Not a controlled environment Unstable work conditions Unknown underground obstructions Mother nature adds challenges



Quality

- What is it?
 - Condition of employment
 - Industry Codes for facility installations
 - API 1104, Appendix A, API 5L, ASME, etc.
 - Our Customers have construction specifications
 - Contractors have processes and procedures
 - Develop project specific procedures
 - Its our reputation
- Cost more to do it twice.

Than to just do it right the first time



Right of Way

We don't view the right of way in full detail during bidding process – typically we spend 1 to 2 days at the job site looking at the job
Right of way widths
Extra work space
Ground conditions
Under ground obstructions





Pipe

- Construction Contractors don't typically inspect the pipe until we receive it on the right of way
 - Out of roundness
 - Ends not square
 - Seams not ground back far enough
 - Bevel consistency and care
 - Gauss (Magnetism)
 - Varying pipe metallurgy (within API 5L)
 Tensile strength for X-70 (75,000 to 105,000)
 Multiple plate manufacturers




Coating cutback to small or to large



Welding

Pipe issues cause additional challenges May use standard welding procedures May use project specific welding procedures (Mechanized – Appendix A or SMAW) Issues we have encountered this year Excessive High/Low Higher repair rates





Welding


Items critical to the welding process Consumable selection and control Bevel preparation Preheating of the pipe Spacing / Gap for root bead Inter pass temperatures Travel speed / amperage / voltage (Heat Input) Training of personnel Pipe mill (QC) / NDT CWI / Welder Sunland Construction, Inc.



Coating

Field joints Coating cutback to small or to large Surface preparation Sand blasting Preheating Application Verification of correct coating thickness Visual Inspection Jeeping







Backfill

Ditch preparation Pipe support in the ditch Padding Sand bags Installation techniques Backfill (prevent dents/ovality) Padding Rockshield Overburden (placing cuts back) Pipe Design (wall thickness)



How do we achieve Quality

- How did we meet some of these challenges
 Developed better Quality Control / Quality Assurance processes
 Highlighting the items of a critical nature
- Developed ITP's (Inspection and Testing Plans)
- Better Planning
- Better Communication

(Owner/Contractor/Inspector)







Inspection & Testing Plan

ITP's



Sunland Construction, Inc.

ITP-04

QC FIELD INSPECTION AND TEST PLAN

Lay Procedure

ltem No.	Activity	Project Procedure	Frequency	Acceptance Criteria	Sunland Responsibility	Representative Responsibility	Action/Record
3	Pipe Inspection	Section 2.0	Each joint	Pipe free of debris	Welding Foreman		●Swab each joint ●No record
5	Verify Weld Procedure	Section 2.0 & Weld Procedures	As needed	Applicable weld procedure	Welding Foreman		 Determine proper weld procedure & notify welders Welder Foreman Report
6	Verify Qualified Welders	Section 4.0 thru 7.0	Prior to welding, at change of Welder and/or Weld Procedure	49 CFR Section 195/Welder Qualification Log	Welding Foreman		 Verify welders qualified to procedure per Welder Qualification Log Welder Foreman Report
7	Bevel Prep	Weld Procedures	Each joint	Clean bevel per Weld Procedure	Welding Foreman		●Buff bevel ●No record
8	Pre heat	Weld Procedures	Each joint	Minimum of 250° F Verified by temp stick or equal.	Welding Foreman		Pre heat bevelNo record
9	Line up	Weld Procedures	Each joint	Root opening 1/16" Seams 2"-4" offset High-low 1/8" & Weld Procedure	Welding Foreman		 ●Use of internal line up clamp, seam roller ●No record
10	Weld Acceptance	Weld Procedures & NDE Procedure	Each weld	Weld procedures, API 1104 & Welding Specification NDE Procedures	Welding Foreman	X	 Visual and NDE Inspection NDE report

Sunland Construction, Inc.

ITP-05 QC FIELD INSPECTION AND TEST PLAN Coating Procedure

ltem No.	Activity	Project Procedure	Frequency	Acceptance Criteria	Sunland Responsibility	Representative Responsibility	Action/Record
12	Surface prep, (blasting)	Section 9.0	2 per shift	1.5 – 4 mils per CCSI SSC-SP10	Coating Foreman		 Blast and check profile Daily coating foreman report
13	Surface prep, (heating)	Section 10.0	Each joint	460° F (approximately) Verified with temp stick or equal	Coating Foreman		 Pre-Heat Joint No record
14	Coating thickness	Section 10.0	2 per shift	14 – 18 mils, 1" overlap 4 readings/joint	Coating Foreman	X	 Check with Elcometer™ Daily coating foreman report
15	Holiday detection	Section 10.0	Each joint	No jeeps	Coating Foreman	X	 Use holiday detector Confirm voltage setting Daily coating foreman report
16	Pipe Coating Inspect	D.O.T. 49 CFR 195	Each joint	No damage 49 CFR 195.23 8(b)	Coating Foreman		 Visual Inspect No record
17	Coating repair	Section 10.0	As needed	<1" – patch stick >1" – 2-part epoxy (20-30 mils)	Coating Foreman	X	 Repair with patch stick or 2- part epoxy No Record



