

Clearing, Grading and Restoration

# Expectations

### Agencies











#### Landowners



http://www.coastalgaslink.com/engagement/landowner-engagement/





- It is necessary to clear the right-ofway of any timber and brush to facilitate pipeline construction.
- Clearing is limited to the approved right-of-way and temporary extra workspace locations.
- Clearing is performed in accordance with Permit Conditions/Agency Consultations/Landowner Agreements



#### **Cutting and Felling**

- In certain geographical locations, it is necessary to hand saw and fell trees before construction in specified periods to protect habitat. The timber is felled in place and ultimately processed during construction.
- During construction, timber can be cut by hand or specialized mechanical equipment.

#### Hand & Mechanical Cutting









#### **Processing**

- Timber is de-limbed and stacked on the right-of-way for removal or placed to the side of the right-ofway to accommodate landowner agreements.
- Limbs and brush are stacked in anticipation of disposal.

#### Stacking











#### **Processing**

- In uplands, stumps are either removed and stacked for disposal or ground in place. This is known as grubbing.
- In wetlands, stumps are left in place to protect the ecosystem.
- Stumps may be removed in the travel lane of the wetland to facilitate the use of construction matting with approval of environmental agencies.

#### Grubbing





#### **Disposal**

 Limbs and brush are disposed of by burning or chipping/grinding.

Log Removal, Burning, and Grinding Activities









#### **Disposal**

- Chips and Grindings may be left on the right-of-way up to the maximum pounds per acre specified in the applicable permits.
- Chips and Grindings may also be hauled offsite if required by the construction permits.
- Once disposal is complete, the rightof-way is ready for grading activities.

#### Grinding, Chip Removal, and Final Clearing











#### Preparation of a safe working surface

- To prepare a safe, level working surface for construction activities, it is necessary to grade the work site.
- Natural drainage patterns are preserved to the extent possible.
- Care is given to place soil graded to prepare a safe working environment within the certificated right-of-way and approved extra workspace locations.
- Erosion control devices are installed to control storm water runoff during construction.

Grading and installation of erosion control devices





#### **Topsoil Segregation**

- Topsoil is stripped, segregated, and preserved in residential and agricultural areas and other areas where requested by a land management agency or landowner.
- Generally, topsoil is removed to its actual depth, up to a maximum of 12 inches, and stockpiled separately from the subsoil that will be excavated from the pipeline trench.
- Topsoil may also be segregated from the entire right-of-way width in areas of actively cultivated, rotated croplands, pastures, hayfields, and where requested by the landowner.
- Segregation of topsoil maintains soil fertility and preserves the native seed bank. Segregation also helps to avoid mixing of topsoil and subsoil and compaction, both of which can reduce soil productivity. Segregation also facilitates timely restoration.

#### Topsoil segregation





#### **Matting**

- To travel through designated wetlands, it is necessary to install timber mats
- Timber mats may also be used in areas with saturated soils to provide a safe and sturdy travel lane in the construction right-of-way.
- Mats are also used to provide a firm travel surface for access to the right-of-way and in work pad locations.

Matting for Access & on ROW in Wetland or Saturated Soil Areas










### **Restoration Considerations**



- Sensitive habitats and wetlands, archaeological sites, and topological features such as steep hills and side slopes
- Permit Conditions/Agency
  Consultations/Landowner Agreements
- Seasonal Construction Schedule and Changes
- Land Uses and Region of the Country
- Soil and Weather Conditions, existing, during construction, and post construction
- Soil Amendments
- Seed Mixes, Seed bed Preparation, and Availability
- Success Criteria and Expectations




### **Restoration Activities**



## Restoration Planning

- Revegetation recommendations
  - FERC defers to federal, state, and local agencies for project- and area-specific recommendations
  - Project sponsors seek input and recommendations for inclusion into project planning and construction

- FERC provides guidance (not sitespecific)
  - Uplands
  - Wetlands



## **FERC Guidelines**

| FERC GUIDELINES                             | UPLANDS | AG LANDS | WETLANDS  | STREAMS                       | RESIDENTIAL |
|---|---------|----------|---|-------------------------------|-------------|
| Erosion controls/<br>BMPs                   | X       | Х        | X   | X                             | Х           |
| Topsoil segregation                         |         | X        | Non-<br>saturated   |                               | Х           |
| Decompaction                                |         | Х        |   |                               | X           |
| Mulch                                       | X       |          |   |                               | Х           |
| Remove excess rock                          |         | X        |   |                               | X           |
| Soil additives (amendments)                 | X       | X        |   |                               | X           |
| Trench breakers                             | X       | X        | X<br>(Up-slope of<br>wetlands)  | X<br>(Up-slope of<br>streams) | Х           |
| Slope breakers<br>(temporary/<br>permanent) | X/X     | Depends  | Installed up-slope of resource on slopes > 5% and < 50 feet from resource |                               | Depends     |



## **FERC Guidelines**

| FERC GUIDELINES   | UPLANDS                     | AG LANDS                                  | WETLANDS  | STREAMS                                      | RESIDENTIAL                          |
|---|-----------------------------|---|---|--|--------------------------------------|
| Final grade, soil replacement, install permanent erosion controls | 20 days<br>from<br>backfill |   |   |  | 10 days from<br>backfill             |
| Seeding (within days of backfill)                                 | 6 days                      |   |   |  | Immediately<br>following<br>backfill |
| Revegetation success (with desirable species)                     | Similar to off-ROW          | Similar to<br>off-ROW<br>(crop<br>yields) | 80% of pre-<br>construction<br>or adjacent<br>ROW | Similar to<br>off-ROW<br>(native<br>species) |                                      |

#### Temporary Erosion Control Measures and Stabilization

- Method primarily determined by
  - Soil type and condition
  - Slopes
- Other factors include
  - Longevity
  - Weather
  - Timing
  - Water availability and logistics
  - Access
  - Proximity to sensitive resources
  - Slip potential



# Temporary Erosion Control Measures and Stabilization

- Protection of topsoil from loss
- Protection of off ROW areas
- Stabilize soils until permanent erosion measures are put in place and restoration is achieved
  - Slope breakers, trench plugs, sediment barriers, ECDs, mulch
  - Quick germinating seasonal species and permanent vegetation seeds are utilized









# Permanent Erosion Control Measures and Restoration

- Fully stabilized soils
- Properly installed slope breakers and trench breakers
- Density and cover are similar on ROW to off ROW
  - Agency comments or permit conditions may impact
- Identify key areas for long-term monitoring
  - Steep slopes
  - Poor in situ soils
  - Areas upslope to meandering streams
  - Invasive/noxious weed species









### **Seed Mixes**

- Use restoration, soils, and vegetation specialists to support early agency/landowner consultations
- Amend soil, de-compact as required, and proper seed bed preparation impacts overall vegetative success
- Where the seed comes from and how fresh the seed is will determine viability
- Verify project magnitude with availability of seeds/plantings at least one year prior to construction



# Revegetation

**Native Species/Pollinators** 



https://www.usda.gov/media/blog/2013/06/20/nrcs-helps-provide-pollinator-habitat-along-sd-highway

**Stabilization Species** 



Sodding Residential Areas





#### Transition from Short-Term Stabilization to Permanent Restoration







### Agricultural Lands

#### **Agricultural Concerns**

- Soils compaction
- Mixing soil layers
  - Utilize topsoiling (double ditching)
- Drian tiles, laser leveling, irrigation
- Soil fertility changes
- Invasive weeds
- Poor yields
- Stabilize soils (surface roughing)





### Agricultural Lands

#### **Permanent Restoration**

- Repair drain tiles
- Typically, no permanent slope breakers
- De-compact soils
- Return top soils
- Landowner plants crops
- Control of Nuisance species



https://www.transcanada.com/en/commitment/landowners

### Steep Slopes

#### **Temporary Stabilization**

- Control of surface and subsurface water with trench and slope breakers
- Proper compaction
- Revegetate and establish rooting to reduce erosion
- Spoil pile placement and weighting, snow, and brush management
- Soil drying and amendments
- Monitoring and early identification of issues








### Steep Slopes

#### **Permanent Restoration**

- Early and continuous monitoring to ensure small issues do not grow
- Surface and subsurface water management converted to permanent
- Ensure revegetation; re-seed and reamend soils as needed



### **Wetlands Restoration**

#### **Permanent Restoration**

- Remove mats
- Restore contours to original wetland hydrology
- Install trench breakers in adjacent uplands to prevent wetland drainage
- Follow project-specific wetland restoration plan
- Until a project-specific plan is developed/ implemented, temporarily revegetate with annual ryegrass



https://www.aboutpipelines.com/en/blog/saving-canadas-wetlands-a-conservation-group-thats-working-with-pipeline-





### Stream Bank Stabilization

#### **Stream Concerns**

- Construction windows for stream (minor, intermediate, major)
- Minimize impacts to woody vegetation on streambanks (leave stumps, matt over existing vegetation)
- Minimize use of riprap to areas where flow conditions limit effective revegetation
- Species safe erosion control fabrics to prevent entrapment of wildlife
- Flow maintenance of the stream during construction







## Monitoring and Vegetation Maintenance

| FERC GUIDELINES                         | UPLANDS  | AG LANDS  | WETLANDS                                     | STREAMS  | RESIDENTIAL   |
|---|--|---|--|--|---|
| Inspections/ Monitoring                 | At least<br>after 1st<br>and 2nd<br>growing<br>seasons | At least after<br>1st and 2nd<br>growing<br>seasons | Annually until<br>success<br>criteria is met |  | At least after<br>1st and 2nd<br>growing<br>seasons |
| Mowing 10-foot width over<br>Centerline | Annual   | Annual  | Annual                                       | Annual<br>(riparian<br>buffer)                         | Annual  |
| Full-Width ROW Mowing                   | 3 years<br>(not more<br>than)                          | 3 years<br>(not more<br>than)                       | Not Allowed                                  | Not allowed;<br>Maintain 25-<br>foot riparian<br>strip | 3 years<br>(not more than)                          |

Vegetation maintenance not to be conducted during certain species windows that could impact migratory patterns or breeding, rearing and nest departure




# Monitoring and Vegetation Maintenance

| FERC GUIDELINES  | UPLANDS                        | AG LANDS | WETLANDS    | STREAMS     | RESIDENTIAL |
|--|--------------------------------|----------|-------------|-------------|-------------|
| Tree Removal within 15 feet of Centerline  | Depends                        | Depends  | Annual      | Annual      | Depends     |
| HDDs   | Depends                        | Depends  | Not allowed | Not allowed | Depends     |
| Time of Year<br>Restriction (migratory birds<br>nesting season)  | Apr 15 - Aug 1                 |          |             |             |             |
| Control unauthorized off-<br>road vehicle use, and<br>maintain signs, gates, and<br>permanent access roads | Life of project<br>(as needed) |          |             |             |             |

### **External Factors**

- Invasive species control is a condition of the Certificate
- Cattle, deer, geese, and other species
- Third-party use (ATVs, hunters)
- Weather
  - · Water too little or too much
  - Heat or cold





### Transition to Maintenance and Monitoring

- Temporary erosion control devices are replaced with permanent ECDs
- Monitor permanent erosion controls until revegetation success criteria have been met
- Remove bridges, consider longterm bridges/access for problematic areas
- Install fences/gates
- Permit releases and Close-outs





## Post Construction Agency Reporting

- FERC 7c Quarterly Reporting,
  Third Party Program
- FERC Blanket Projects Annual Reporting
- On-going monitoring of restoration using aerial and ground line patrols

